



**DRAWWORKS**

- Midway 600 w/ 1020MM Kobelt Brake
- CAT 3406 TA w/ 6 speed Allison transmission
- Width 3.7M
- Length 22,1M
- Font 29,500KG
- Back 52,000 KG

**MAST**

- Steelhead 72' (22M) 285 000 Lb
- (130,000 daN) capacity

**SUBSTRUCTURE**

- Trailer mounted w/ 12 Height" high-back working floor and hydraulic leveling system

**MUD PUMPS**

- Dual Emsco F1000 triplex w/ 6 1/2" (155mm) bore X 10" (254mm) stroke w/ caterpillar CAT 3412 x2
- Width 3.70M
- Length 12.25M
- Height 3.50M
- 39,185 KG

**MUD TANK**

- 400 bbl (70m3) w/ low pressure mixing complete w/ Dual King Cobra Shaker
- Width 3.65M
- Length 18M
- Height 3.2M
- 39,480KG

**LIGHT PLANT**

- 450 KW w/208 volt and 480 volt
- 800 KW w/ 600 volt
- Width 3.8M
- Length 16.8 M
- Height 3.65M
- 48,700KG

**BLOW OUT PREVENTORS (CLASS #3)**

- 2x8' (11"bore), 3000psi (203 mm, 21000 kPa) Townsend LWP single gates
- 1x8", 3000 psi (203mm, 21000 kPa) Townsend Spherical

**ROTARY TABLE**

- 18" (457 mm) TSM

**CHOKE MANIFOLD**

- 76mm X 21,000 kPa

**ACCUMULATOR**

- 300M Koomey air/hydraulic w/ nitrogen back up with single pump

**BOILER**

- 100H.P. Volcano
- Width 3.65M
- Length 12.3M
- Height 3.55M
- 28,150KG

**DRILL PIPE**

- 4.5", 16.6#
- S135, Range 3 - DS 40 Connections

**HWDP**

- 4.5" Range 3
- DS 40 Connections

**Collars**

- 5" - 127mm w/ DS38 Connections
- 6 1/4" - 159mm w/ 4 1/2 H90 Connections

**HYDRAULIC PIPE TUBS**

- Two (2)
- Width 2.8M
- Length 18.3M
- Height 1.3M

**MANUAL PIPE TUBS**

- Three (3)
- Width 3.65M
- Length 13.8M
- Height 3.7M
- 33,490 KG

**CAT WALK HYDRAULIC SKATE**

- Width 3.4M
- Length 18.9M
- Height 1M
- 20,180KG

**FUEL CAPACITY**

- 16 800 Litres

**PIPE PULL DOWN SYSTEM**

- 20,000 lbs/10,000 daN



**TEMPCO DRILLING COMPANY INC**

**RIG #10 Top Drive Range III (Warrior 175 Ton)**

**Capacity 3500 (M)**

**WINTER LOADS: 17**

**SUMMER LOADS: 16**