



DRAWWORKS

- Corsair 400w/1020mm w/1020 MM
- Kobelt Brake
- Caterpillar 3406 w/ 5 speed Allison transmission
- Width 3.8M
- Length 9.8M
- Front 21,000KG
- Back 41,000 KG

MAST

- Steelhead 72' (22M) (110,000 daN) Capacity

SUBSTRUCTURE

- Trailer Mount w/ '12 Height "High-back" working floor and hydraulic leveling system 3.6 x 19.3

MUD PUMP

- Emsco F1000- triplex 61/2" (254mm) stroke w/ caterpillar C27 1,050 hp x2
- Width 3.8M
- Length 12.25M
- Height 3.16M
- 39,000 KG

HPU - W -3.1 x L-9.3 x H-2.8

MUD TANK

- 107.4m3 Shaker x2(KING COBRA)
- Width 3.51M
- Length 16.75M
- Height 3.82M
- 35,000 KG

LIGHT PLANT

- 350 KW w/ 280 volt and 480 volt, 3406 Caterpillar compatible for centrifuge
- Width 3.65M
- Length 11.27M
- Height 2.9M
- 24,490KG

BLOW OUT PREVENTORS (CLASS #3)

- 2x8' (9"bore), 3000psi (203 mm, 21000 kPa) Shaffer LWP single gates
- 1x8", 3000 psi (203mm, 21000 kPa) Shaffer Spherical

LOADER

ROTARY TABLE

- 18" (457 mm) Howard Turner

CHOKE MANIFOLD

- 76mm X 21,000 kPa

ACCUMULATOR

- Air Hydraulic w/nitrogen back up single pump

BOILER

- 80 H.P. Volcano
- Width 3.39M
- Length 9.93M
- Height 3.06M
- 28,150KG

DRILL PIPE (4" on all rigs) (GRADE X95)

- Available Pipe:
- 4"-102mm-4" FH connections
- 4" hevi-wate - 102mm 4"FH
- 15- 5" - 127mm w/ 3 1/2 IF Connections
- 6 1/4 - 159mm w/ 4 1/2 H90 Connections

HYDRAULIC PIPE TUBS

- Two (2)
- Width 2.7M
- Length 12.10M
- Height 1.2M

WATER TANK

- Width 3.40M
- Length 12.78M
- Height 3.8M
- 39,160 KG

HYDRAULIC SKATE CAT WALK

- Width 2.74M
- Length 18.36M
- Height 3.0M
- 20,180KG

AUXILIARY EQUIPMENT

- Pason EDR

FUEL CAPACITY

- 11 602 Liters
- CAODC Inventory #1389

PUSH SHACK - 3.6 x 17.5 x 3.1

PULL DOWN SYSTEM

- 20,000 lbs/ 10,000 daN

TEMPCO DRILLING COMPANY INC.

RIG #3TD TOP DRIVE RANGE III FDS 150 TON

HPU UNIT C11 420HP

Capacity (M) 3000M

WINTER LOADS: 15

SUMMER LOADS: 14

